

ADDENDUM NO. 1
TO
CITY OF AUBURN, MAINE
2026 95 Main Street Drainage Project BID#2026-008
DATE: 9/26/2025

This addendum amends and /or supplements the bid documents as indicated below. Only these items alter the bid documents. Any verbal discussions or responses are hereby declared null and void. Please acknowledge this addendum on the Bid Proposal Form.

Q: Is the milling required for both the parking and roadway?

A: Yes.

Q: Can the full job be completed in 2025?

A: Yes, however trenches will be inspected in 2026 for settlement and quality.

Q: Is there a spot for staging nearby?

A: The entire parking area within this 95 Main Street address will be closed to parking to allow for staging in the southern spots.

Q: Can you provide a detail for the brickwork?

A: The brick should be the Pine Hall Pathway Paver Brick. Build up from subgrade shall be 8" of MDOT Type A Gravel, 2 inches of HMA (can be placed in one lift), can use a sand-asphalt setting bed and then brick to match curb elevation. Setting over cured concrete can be acceptable with submittal approval.

Q: What is the budget?

A: \$85,000.00.

Q: Are you looking for new bricks to build the sidewalk?

A: Yes